BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT35697

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/03/2019-20, Date: 14.05.2019

Filling of potholes in ward 07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )	
				In Figures	In Words
1	1612.5	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 142 / Item No. 19.1/	cum	73.88	Rupees Seventy Three and Eighty Eight Paise Only
2	1209.38	KSSRB M 400-17: Providing laying, spreading and compacting graded fine aggregate to wet mix macadam specificationns including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surfce and compating with vibratory roller to achieve the desired density complete as per specifications. MORTH specifications no. 406(P-155., It No: 20.18)	cum	1701.08	Rupees One Thousand Seven Hundred One and Eight Paise Only
3	322.5	Filling pot holes and patch repairs with bituminous concrete 40mm. KSRRB M3000-5.Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.30, back filling the potholes with hot bituminous materail as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continous surface all as per clause 3004-2, complete as per specifications, MORTH specifications No.3004-2. (Page No. 259 and item No. 35.5)	sqm	310.88	Rupees Three Hundred Ten and Eighty Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92